



1. ALL FLOOR DRAIN-OPEN DRAIN IN MECHANICAL EQUIPMENT ROOMS TO BE JCSM N230003-E1 OR EQUAL.

1. DOWNSTREAM CONTRACTOR SHALL CO-ORDINATE HIS WORK WITH THAT OF ALL OTHER TRADES.
2. ALL PIPING TO BE RUN FITTED TO DESIGN.
3. ALL FIRE DEPARTMENT HOSE CONNECTIONS SHALL HAVE THREADS CONFORMING TO THOSE OF THE LOCAL FIRE DEPARTMENT.
4. ALL CONTROL VALVES SHALL BE INSTALLED WITH TAMPER SWITCHES.
5. ALL ELECTRICAL DEVICES SHALL BE COMPATIBLE WITH FIRE ALARMS.
6. ALL SPRINKLER PIPING TO BE RUN CONCEALED ABOVE THE CEILING EXCEPT IN MECH. ROOMS WHERE PIPING IS TO BE RUN EXPOSED AT THE CEILING.
7. CAPPED SPRINKLER CONNECTIONS HAVE BEEN PROVIDED FOR CONNECTION TO THESE SHARED CONNECTIONS WITH SPRINKLER PIPING FOR TENANT AREA AFTER FINAL TENANT LAYOUT HAS BEEN DETERMINED. FINAL LAYOUT OF SPRINKLER PIPING SHALL BE CO-ORDINATED WITH LIGHTING LAYOUT & WITH THAT OF ALL OTHER TRADES.

TYPICAL FLOOR PLAN (2ND THRU 10TH FLOORS)

3/19/79 FOR CONSTRUCTION

date
1-10-79

job number
77057

sheet number
13-4